

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

ORIGINAL

FIELD NOTES

OF THE

DEPENDENT RESURVEY OF A PORTION OF THE
PYRAMID LAKE INDIAN RESERVATION BOUNDARY
AND A PORTION OF THE SUBDIVISIONAL LINES,
AND A METES-AND-BOUNDS SURVEY OF PORTIONS OF THE
LYON AND STOREY COUNTY LINE,
TOWNSHIP 20 NORTH, RANGE 24 EAST,
OF THE MOUNT DIABLO MERIDIAN,
IN THE STATE OF NEVADA

EXECUTED BY

Richard J. Dieckmann, Cadastral Surveyor


Under Special Instructions dated October 30, 2025,
and approved October 30, 2025,
which provided for the surveys included under Group No. 1032,
and Assignment Instructions dated October 30, 2025.

Survey commenced November 3, 2025

Survey completed July 23, 2026

INDEX DIAGRAM

TOWNSHIP 20 NORTH, RANGE 24 EAST, MOUNT DIABLO MERIDIAN, NEVADA



Dependent Resurvey Of A Portion Of The
Pyramid Lake Indian Reservation Boundary..... pp 3 - 6
Metes-And-Bounds Survey Of Portions Of The
Lyon And Storey County Line pp 20 - 22

TOWNSHIP 20 NORTH, RANGE 24 EAST, MOUNT DIABLO MERIDIAN, NEVADA

CHAINS

The following field notes are those of the dependent resurvey of a portion of the Pyramid Lake Indian Reservation Boundary and a portion of the subdivisional lines, and a metes-and-bounds survey of portions of the Lyon and Storey County Line, Township 20 North, Range 24 East, Mount Diablo Meridian, Nevada.

1865 - The Pyramid Lake Indian Reservation Boundary was surveyed by E.B. Monroe.

1865 - The Fourth Standard Parallel North, through Range 24 East, the south, east and west boundaries and a portion of the subdivisional lines were surveyed by U.S. Deputy Surveyor S.W. Foreman, under Contract H.

1878 - A portion of the Pyramid Lake Indian Reservation Boundary was resurveyed, and a portion of the subdivisional lines were surveyed by U.S. Deputy Surveyors J.H. Eaton and D.H. Barker, under Contract No. 84.

1887 - The Pyramid Lake Indian Reservation Boundary, the Fourth Standard Parallel North, through a portion of Range 24 East, and a portion of the subdivisional lines were resurveyed by U.S. Deputy Surveyor P. Powers, under Contract No. 184.

1903 - The south Boundary, a portion of the west Boundary and a portion of the subdivisional lines were resurveyed, and a portion of the subdivisional lines surveyed by U.S. Deputy Surveyor F.H. Criss, under Contract No. 230.

1909-11 - A portion of the subdivisional lines were resurveyed by U.S. Deputy Surveyor R. Gorlinski, under Contract No. 254. The plat approved February 6, 1912, was superseded by the plat approved December 31, 1913.

1911-12 - The Pyramid Lake Indian Reservation Boundary and a portion of the Fourth Standard Parallel North, through a portion of Range 24 East, was retraced, a portion of the subdivisional lines were resurveyed, and certain sections were subdivided by U.S. Surveyor G.P. Harrington, under instructions dated April 27, 1911, and under the direction of Topographer A.F. Dunnington.

1913 - A portion of the subdivisional lines and a portion of the subdivision-of-section lines of section 9 were corrected by U.S. Surveyor F.E. Joy under instructions dated May 10, 1913, and under the direction of Topographer A.F. Dunnington.

1916 - A portion of the Pyramid Lake Indian Reservation, The Fourth Standard Parallel North, through a portion of Range 24 East, a portion of the west Boundary and a portion of the subdivisional lines were resurveyed by U.S. Surveyor H.W. Reppert under Group No. 38.


Other surveys remote to this area are not included.

Before restoring the corners, the lines of the original surveys were retraced and a diligent search made for any evidence of the position of the original corners and other calls of the original field note record.

TOWNSHIP 20 NORTH, RANGE 24 EAST, MOUNT DIABLO MERIDIAN, NEVADA

CHAINS	The rules of proportionate measurement were applied in order to ascertain the position of lost corners, after completing the necessary retracements to connect with identified corner locations. In order to simplify the record, the true line notes only are supplied herewith, which refer to the completed survey. The survey was executed in accordance with the specifications set forth in the Manual of Surveying Instructions, 2009, and the Special Instructions for Group No. 1032, dated October 30, 2025. Measurements were made with Trimble R-12i Global Navigation Satellite System (GNSS) receivers using the real-time kinematic (RTK) method and refer to the true meridian based on geodetic methods. The mean bearings of the lines and horizontal equivalents of ground distances only are entered in the field notes. The NAD 83(2011)(EPOCH:2010.0000) geographic position, of the following corners, was determined from Global Positioning System (GPS) static observations processed by National Geodetic Survey, Online Positioning User Service (OPUS), utilizing Continuously Operating Reference Stations (CORS): AI8816 UPSA UPSA BRGN NV1997 ECCREF DIMPLE DE6254 RNO1 NW RENO COOP CORS ARP DE6260 STEA STEAD COOP CORS ARP DH8860 DOT1 CARSON CITY COOP CORS ARP and carried forward by RTK observations. The corner of sections 19, 20, 29 and 30, is as follows: Latitude: 39°34'43.516" N. Longitude: 119°19'15.819" W. The corner of sections 9 and 10 only, is as follows: Latitude: 39°36'27.961" N. Longitude: 119°16'58.848" W.
--------	--

DEPENDENT RESURVEY OF A PORTION OF THE
PYRAMID LAKE INDIAN RESERVATION BOUNDARY,
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS	Reestablishment of a Portion of the Survey Executed by E.B. Monroe in 1865, a Portion of the Resurvey Executed by U.S. Deputy Surveyor P. Powers in 1887, a Portion of the Resurvey Executed by U.S. Surveyor G.P. Harrington in 1911-12, and a Portion of the Resurvey Executed by U.S. Surveyor H.W. Reppert in 1916 Beginning at the closing cor. of secs. 9 and 16, on the westerly bdy. of the Pyramid Lake Indian Reservation Boundary, hereinafter described. From this cor., Mile Post 1 of the Pyramid Lake Indian Reservation Boundary, bears N. $47^{\circ}53'40''$ W., 76.154 chs. dist., monumented with a basalt stone, 14x12x10 ins. (1911-12 Record: 14x8x6 ins. above ground), firmly set, flush with the ground, mkd. PL on SW. face and 1M on NW. face; NE. and alongside is the witness cor. to Mile Post 1, monumented with a heavily oxidized iron post, 36 ins. long, 1 in. diam., firmly set, projecting 2 ins. above the ground and bent to the NE., with brass cap mkd. as described in the field notes of the 1911-12 resurvey of the Pyramid Lake Indian Reservation Boundary, executed under instructions dated April 27, 1911. At the corner point Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 23 ins. in the ground, over a plastic-encased magnet, in a collar of stone, with brass cap mkd.  2025 Add marks AM to the stone and bury inverted alongside the stainless steel post. The witness cor. to Mile Post 1 no longer functions as a witness cor., remark the brass cap AM 2025 and the recovered top 30 ins. of the iron post was inverted inside the stainless steel post as a memorial to the true point. This control line was fully retraced and a careful search was made for evidence of the intervening corners, none of which were found. S. $47^{\circ}53'40''$ E., on the westerly bdy. of the Pyramid Lake Indian Reservation Boundary. 2.827 Mile Post 2 of the Pyramid Lake Indian Reservation Boundary, monumented with a basalt stone, 20x10x9 ins. (1911-12 Record: 16x8x8 ins. above ground), lying on its side on top of the ground, mkd. 2M on a face, PL on a face, with a mound of stone, 6 ft. diam., 1 1/2 ft. high, SE. of the stone; lying loose alongside is the witness cor. to Mile Post 2, an iron post, 36 ins. long, 1 in. diam., with brass cap mkd.
--------	--

DEPENDENT RESURVEY OF A PORTION OF THE
PYRAMID LAKE INDIAN RESERVATION BOUNDARY,
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS	
	2M PLIR 1911 At the corner point Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 15 ins. in the ground, over a plastic-encased magnet, in a mound of stone, 5 ft. base, to top, with brass cap mkd. T20N PLIR S16 2M R24E 2025 Bury the stone alongside the stainless steel post. The witness cor. to Mile Post 2 no longer functions as a witness cor., and the iron post was buried horizontally alongside the stainless steel post in the mound of stone as a memorial to the true point. S. 47°48'10" E., on the westerly bdy. of the Pyramid Lake Indian Reservation Boundary. 0.479 The witness point on the westerly bdy. of the Pyramid Lake Indian Reservation Boundary, at intersection with the Lyon and Storey County Line, hereinafter described. 5.00 Rocky Draw, drains S. 25° W. 15.40 Draw, drains W. 20.70 From this point, the remains of a mound of stone, 6 ft. diam., 2 ft. high, bears N. 42° E., 0.25 chs. dist. (1887 Record: E.) 21.30 Rocky ridge, bears S. 25° E. and N. 25° W. 28.235 Station 2 of the Pyramid Lake Indian Reservation Boundary, monumented with a basalt stone, 15x15x8 ins. (1911-12 Record: granite, 10x10x10 ins. above ground), firmly set, projecting 9 ins. above the ground, mkd. S2 PLIR on N. face and a cross mark off center on the top, with a mound of stone 6 ft. diam., 2 ft. high, N. of the stone, from which the 1887 bearing object A rock outcrop, 10x6x3 ft., bears S. 72°10' E., 41.7 lks. dist. (1887 Record: S. 73°10' E., 40 lks. dist.), mkd. with a cross on the westerly face. The volcanic 1887 mkd. stone set in the N. face of the mound of stone and the 1911-12 witness cor. monument were searched for and not recovered. At the corner point

DEPENDENT RESURVEY OF A PORTION OF THE
PYRAMID LAKE INDIAN RESERVATION BOUNDARY,
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS	Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 20 ins. in the ground, over a plastic-encased magnet, in a mound of stone, 6 ft. base, to top, with brass cap mkd.  T20N R24E S16 2025 Bury the stone alongside the stainless steel post in the mound of stone. N. 27°29'00" E., on the easterly bdy. of the Pyramid Lake Indian Reservation Boundary. 7.60 Draw, drains N. 55° E. 11.144 Mile Post 2 1/2 of the Pyramid Lake Indian Reservation Boundary, monumented with a vesicular basalt stone, 14x13x9 ins. (1911-12 Record: granite, 12x12x12 ins. above ground), firmly set, projecting 10 ins. above the ground, mkd. 2 1/2 M on SW. face, PL on E. face, with an embedded mound of stone 4 ft. diam., NE. of the stone. The 1911-12 witness cor. monument was searched for and not recovered. At the corner point Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 20 ins. in the ground, over a plastic-encased magnet, in a mound of stone, 5 ft. base, to top, with brass cap mkd.  2025 Bury the stone alongside the stainless steel post. Cor. is located on the top of a spur, extending N. 60° E. along the downhill spine. N. 27°44'50" E., on the easterly bdy. of the Pyramid Lake Indian Reservation Boundary. 12.630 The closing cor. of secs. 9 and 16 on the easterly bdy. of the Pyramid Lake Indian Reservation Boundary, hereinafter described.
--------	---

DEPENDENT RESURVEY OF A PORTION OF THE
PYRAMID LAKE INDIAN RESERVATION BOUNDARY,
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS

From this cor., Mile Post 3 of the Pyramid Lake Indian Reservation Boundary, bears N. $27^{\circ}44'50''$ E., 27.065 chs. dist., monumented with an iron post, 36 ins. long, 1 in. diam., firmly set, projecting 12 ins. above the ground, established as a witness cor. in the field notes of the 1911-12 resurvey of the Pyramid Lake Indian Reservation Boundary, executed under instructions dated April 27, 1911, and accepted as the corner in the 1916 retracement and resurvey of portions of the Pyramid Lake Indian Reservation Boundary, executed under instructions dated July 9, 1915, with brass cap mkd.



1911

The 1887 stone was searched for and not recovered.

At the corner point

Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 28 ins. in the ground, over a plastic-encased magnet, in a collar of stone, with brass cap mkd.

PLIR / T20N
3 M / S 9
/ R24E

2025

The witness cor. to Mile Post 3 no longer functions as a witness cor., and the iron post is inserted inside the stainless steel post as a memorial to the true point.

DEPENDENT RESURVEY OF A PORTION OF THE SUBDIVISIONAL LINES
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS	Reestablishment of a Portion of the Survey Executed by U.S. Deputy Surveyor S.W. Foreman in 1865, a Portion of the Survey Executed by U.S. Deputy Surveyors D.H. Barker and J.H. Eaton in 1878, a Portion of the Resurvey Executed by U.S. Deputy Surveyor P. Powers in 1887, a Portion of the Resurvey and Survey by U.S. Deputy Surveyor F.H. Criss in 1903, a Portion of the Resurvey Executed by U.S. Surveyor G.P. Harrington in 1911-12, a Portion of the Resurvey Executed by U.S. Surveyor F.E. Joy, in 1913, and a Portion of the Resurvey Executed by U.S. Surveyor H.W. Reppert in 1916 From the cor. of secs. 15, 16, 21 and 22, monumented with a basalt stone, 21x15x10 ins. (1916 Record: 18x12 ins. above ground), lying on its side flush with the ground, mkd. T20N on downward face, R24E on upward face, and 3 horizontal grooves on the edge of the stone opposite the other marks. At the corner point Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 20 ins. in the ground, over a plastic-encased magnet, in a mound of stone, 4 ft. base, to top, with brass cap mkd. T20N R24E <table border="1"> <tr> <td>S16</td><td>S15</td></tr> <tr> <td>S21</td><td>S22</td></tr> </table> 2025 Bury the stone in the mound of stone alongside the stainless steel post. N. 0°11'50" W., bet. secs. 15 and 16. 2.85 Overhead power lines, extend N. 15° E. and S. 15° W. 9.870 From this point, a point established as a property cor., by Steven E. Hampton, Nevada Professional Land Surveyor No. 10142, in 2005, bears E., 0.003 chs., dist., monumented with a rebar, 5/8 in. diam., firmly set, projecting 1 in. above the ground, with a steel "T" post alongside, as recorded in Lyon County, Nevada, Subdivision Map, File No. 356272. 18.498 A point established as a property cor., by Steven E. Hampton, Nevada Professional Land Surveyor No. 10142, in 2005, monumented with a rebar, 5/8 in. diam., firmly set, projecting 2 ins. above the ground, as recorded in Lyon County, Nevada, Subdivision Map, File No. 356272. 21.323 A point established as a property cor., by Steven E. Hampton, Nevada Professional Land Surveyor No. 10142, in 2005, monumented with a rebar, 5/8 in. diam., firmly set, projecting 8 ins. above the ground, with an oxidized yellow plastic cap, with illegible marks, as recorded in Lyon County, Nevada, Subdivision Map, File No. 356272.	S16	S15	S21	S22
S16	S15				
S21	S22				

DEPENDENT RESURVEY OF A PORTION OF THE SUBDIVISIONAL LINES
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS	
24.149	A point established as a property cor., by Steven E. Hampton, Nevada Professional Land Surveyor No. 10142, in 2005, monumented with a rebar, 5/8 in. diam., firmly set, projecting 7 ins. above the ground, in an aluminum vent cover collar, 16 ins. square, as recorded in Lyon County, Nevada, Subdivision Map, File No. 356272.
29.632	From this point, a point established as a property cor., by Steven E. Hampton, Nevada Professional Land Surveyor No. 10142, in 2005, bears W., 0.003 chs. dist., monumented with a rebar, 5/8 in. diam., firmly set, projecting 2 ins. above the ground, with yellow plastic cap pieces in the vicinity of the rebar, and a plastic fencepost, 5 ins. square, alongside, fencelines extending N. and E., as recorded in Lyon County, Nevada, Subdivision Map, File No. 356272.
34.608	A point established as a property cor., by Steven E. Hampton, Nevada Professional Land Surveyor No. 10142, in 2005, monumented with a rebar, 5/8 in. diam., firmly set, projecting 1 in. above the ground, with a plastic fence post, 5 ins. square, alongside, fence lines extending E. and S., as recorded in Lyon County, Nevada, Subdivision Map, File No. 356272.
38.40	Power line access road, 15 lks. wide, bears N. 5° E. and S. 5° W.
39.853	The 1/4 sec. cor. of secs. 15 and 16, perpetuated by person(s) unknown, noted by John C. Nelson, Nevada Registered Land Surveyor No. 4789, in 1979, as shown on a Parcel Map, recorded in Lyon County, Nevada, File No. 51069, monumented with a rebar, 1/2 in. diam., 18 ins. long, firmly set, projecting 1 in. above the ground, in an embedded mound of stone, 2 ft. diam. This position has been utilized by various Nevada Registered/Professional Land Surveyors and is accepted as the best available evidence of the position of the original corner. The notched stone noted in the Nelson survey was searched for and not recovered. At the corner point Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 25 ins. in the ground, over a plastic-encased magnet, in a collar of stone, with brass cap mkd. T20N R24E 1/4 S16 S15 2025 Insert the rebar inside the stainless steel post. N. 0°14'20" W., beginning new measurement.
40.117	The closing cor. of secs. 15 and 16, monumented with a scattered mound of stone, 6 ft. diam. This position correlates well with the measurements reported in local surveys in this area, and is accepted as the best available evidence of the position of the original corner. At the corner point

DEPENDENT RESURVEY OF A PORTION OF THE SUBDIVISIONAL LINES
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS	Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 25 ins. in the ground, over a plastic-encased magnet, in a collar of stone, with brass cap mkd. T20N R24E S 9 S16 S15 CC 2025 From this cor., the cor. of secs. 9 and 10 only, bears N. 89°26'00" E., 3.402 chs. dist. From the cor. of secs. 20, 21, 28 and 29, monumented with a vesicular basalt stone, broken into 2 pieces, total dimensions of 15x11x9 ins. (1903 Record: 12x12x8 ins.), firmly set, projecting 10 ins. above the ground, no marks visible, in a mound of stone, 2 ft. diam., 1 ft. high, with a broken off steel "T" post alongside. This position correlates well with the position accepted by Rick P. Christian, Nevada Professional Land Surveyor No. 11178, as shown on a Subdivision Map, recorded in Lyon County, Nevada, File No. 359993, and is accepted as the best available evidence of the position of the original corner. At the corner point Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 25 ins. in the ground, over a plastic-encased magnet, in a collar of stone, with brass cap mkd. T20N R24E S20 S21 S29 S28 2025 Bury the stone alongside at the base and build a mound of stone 3 ft. base, 1 1/2 ft. high, along the W. side of the stainless steel post. N. 0°09'20" W., bet. secs. 20 and 21. 14.40 Top of ridge, S. 60° E. and N. 60° W. 21.45 Draw, drains S. 70° E. 25.20 Top of ridge, N. 60° E. and S. 60° W. 29.60 Draw, drains N. 60° E. 37.85 Top of ridge, N. 70° E. and S. 70° W. 40.067 The 1/4 sec. cor. of secs. 20 and 21, monumented with a basalt stone, 16x10x10 ins., firmly set, projecting 12 ins. above the ground, mkd. 1/4 on W. face, in an embedded mound of stone, 4 ft. diam. At the corner point
--------	--

DEPENDENT RESURVEY OF A PORTION OF THE SUBDIVISIONAL LINES
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS	Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 23 ins. in the ground, over a plastic-encased magnet, in a mound of stone, 4 ft. base, to top, with brass cap mkd. T20N R24E 1/4 S20 S21 2025 Bury the stone in the mound of stone alongside the stainless steel post. N. 0°10'00" W., beginning new measurement. 3.75 Draw, drains N. 50° E. 5.75 Top of ridge, N. 70° E. and S. 70° W. 23.25 Dry wash, drains N. 15° E. 35.25 Spur, the downhill spine bears N. 35° E. 40.15 Overhead power lines, extend S. 45° E. and N. 45° W. 40.184 The cor. of secs. 16, 17, 20 and 21, monumented with a basalt stone, 14x10x8 ins., (1903 Record: 15x9x7 ins.) firmly set, projecting 11 ins. above the ground, mkd. with 4 notches on E. edge and 3 notches on S. edge, in the easterly edge of a mound of stone, 3 ft. diam., 1 ft. high, with a steel "T" post alongside. At the corner point Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 22 ins. in the ground, over a plastic-encased magnet, in a mound of stone, 4 ft. base, to top, with brass cap mkd. T20N R24E S17 S16 S20 S21 2025 Bury the stone alongside the base and reset the steel "T" post alongside of the stainless steel post. From the cor. of secs. 15, 16, 21 and 22. S. 89°58'50" W., bet secs. 16 and 21. 0.70 Overhead power lines, extend N. 15° E. and S. 15° W. 1.60 Power line access road, 15 lks. wide, bears N. 10° E. and S. 10° W. 15.10 Power line access road, 15 lks. wide, bears S. 80° E. and N. 80° W.
--------	--

DEPENDENT RESURVEY OF A PORTION OF THE SUBDIVISIONAL LINES
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS	
15.35	Top of ridge, bears S. 50° E. and N. 50° W.
16.45	Power line access road, 15 lks. wide, bears N. 85° E. and S. 85° W.
17.20	Power line access road, 15 lks. wide, bears S. 85° E. and N. 85° W.
18.65	Draw, drains S. 10° E.
19.95	Power line access road, 15 lks. wide, bears N. 85° E. and S. 85° W.
27.20	Power line access road, 15 lks. wide, bears S. 65° E. and N. 65° W.
30.10	Top of main ridge, bears S. 10° E. and N. 10° W.
30.25	Power line access road, 15 lks. wide, bears N. 75° E. and S. 75° W.
35.50	Power line access road, 15 lks. wide, bears S. 70° E. and N. 70° W.
39.40	Power line access road, 15 lks. wide, bears N. 70° E. and S. 70° W.
39.988	The 1/4 sec. cor. of secs. 16 and 21, monumented with a vesicular basalt stone, 20x15x6 ins. (1916 Record: 24x14x7 ins.), firmly set, projecting 11 ins. above the ground, mkd. 1/4 on N. face, in a mound of stone, 4 ft. diam., 1 1/2 ft. high. At the corner point Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, over a plastic-encased magnet, with brass cap mkd. T20N R24E S16 1/4 ——— S21 2025 Bury the stone alongside at the base and build a mound of stone 4 ft. base, 1 1/2 ft. high, along the N. side of the stainless steel post. S. 89°57'50" W., beginning new measurement.
4.10	Draw, drains N. 60° W.
9.80	Gas line access road, 20 lks. wide, bears S. 40° E. and N. 40° W.
39.60	Power line access road, 15 lks. wide, bears S. 20° E. and N. 20° W.

DEPENDENT RESURVEY OF A PORTION OF THE SUBDIVISIONAL LINES
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS	
39.847	The cor. of secs. 16, 17, 20 and 21.
	N. 0°09'00" E., bet secs. 16 and 17.
0.50	Power line access road, 15 lks. wide, bears S. 30° E. and N. 30° W.
7.574	Point for a witness point at intersection with the Lyon and Storey County line, hereinafter described.
35.80	Gas line access road, 20 lks. wide, bears S. 45° E. and N. 45° W.
39.15	Draw, drains N. 25° E.
39.841	Point for the 1/4 sec. cor. of secs. 16 and 17 at proportionate distance, there is no remaining evidence of the original corner.
	Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, over a plastic-encased magnet, in a collar of stone, with brass cap mkd.
	T20N R24E 1/4 S17 S16
	2025
	from which
	A granite boulder, 6 ft. long, 3 ft. wide, 1 1/2 ft. high bears, N. 40°42' E., 22.6 lks. dist., mkd. XBO.
	Build a mound of stone, 4 ft. base, 1 1/2 ft. high, along the W. side of the stainless steel post.
75.50	The right bank of an irrigation canal, bears N. 65° E. and S. 65° W.
76.10	The left bank of an irrigation canal, bears N. 65° E. and S. 65° W.
76.60	An irrigation canal access road, 27 lks. wide, bears N. 65° E. and S. 65° W.

DEPENDENT RESURVEY OF A PORTION OF THE SUBDIVISIONAL LINES
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS

79.882

The cor. of secs. 8, 9, 16 and 17, monumented with a basalt stone, 18x8x7 ins. (1916 Record: 10x8x8 ins. above ground), lying on its side, embedded flush with the surface of the ground, and lying on its side under a large sage brush, mkd. with 4 notches on one edge and 4 notches on an adjacent edge, alongside is a point established by Darryl M. Harris, Nevada Professional Land Surveyor No. 6497, in 1990, monumented with a rebar, 5/8 in. diam., 18 ins. long, firmly set, flush with the ground, with an aluminum cap mkd. RLS XXXX 6497 8 9 17 16 and a punch mark in the center, as shown on a Record of Survey, recorded in Storey County, Nevada, Book 77, Page 163, File No. 65322 and Washoe County, Nevada, File No. 1389685. The position of the mkd. stone is substantiated by an on-line distance tie by the United States Geological Survey, Hydrographic Branch Reclamation Service in 1904 from a canal to the corner as shown on Map No. 4735, Drawer No. 273, Sheet No. 4 of 11, with additional reference number 446-15, on file with the Truckee-Carson Irrigation District.

At the corner point

Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 26 ins. in the ground, over a plastic-encased magnet, in a collar of stone, with brass cap mkd.

T20N R24E

S 8	S 9
S17	S16

2025

Insert the rebar inside the stainless steel post.

From this same cor., a steel "T" post, bears S. 73°17' W., 0.171 chs. dist.

From the cor. of secs. 9 and 10 only, monumented with a scattered mound of stone, 6 ft. diam. This position correlates well with the measurements reported in local surveys in this area, and is accepted as the best available evidence of the position of the original corner.

At the corner point

Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 26 ins. in the ground, over a plastic-encased magnet, in a collar of stone, with brass cap mkd.



T20N R24E

S 9	S10
S15	

2025

Cor. is located, N., 15 lks. dist., of a power line access road, 15 lks. wide, bears E. and W.

DEPENDENT RESURVEY OF A PORTION OF THE SUBDIVISIONAL LINES
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS	S. 89°26'00" W., on the S. bdy. of sec. 9.
3.402	The closing cor. of secs. 15 and 16.
14.039	Intersect the easterly bdy. of the Pyramid Lake Indian Reservation Boundary.
	The true point for the closing cor. of secs. 9 and 16, at intersection of the line between secs. 9 and 16, with the easterly bdy. of the Pyramid Lake Indian Reservation Boundary.
	Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 25 ins. in the ground, over a plastic-encased magnet, in a collar of stone, with brass cap mkd.
	 2025
	Build a mound of stone, 4 ft. base, 1 1/2 ft. high along the E. side of the stainless steel post.
	From this point, a position monumented as the closing cor. of secs. 9 and 16 on the easterly bdy. of the Pyramid Lake Indian Reservation Boundary, during the 1887 resurvey, bears S. 71°12'20" W., 0.108 chs. dist., monumented with a vesicular basalt stone, 14x12x10 ins. (1911-12 Record: 14x8x6 ins. above ground), firmly set, projecting 8 ins. above the ground, mkd., CC on SE. face, PLIR on NW. face, with a mound of stone, 4 ft. diam., 1 ft. high, along the S. side; W. of and alongside is the witness cor. to the 1887 closing cor. of secs. 9 and 16 on the easterly bdy. of the Pyramid Lake Indian Reservation Boundary, an iron post, 36 ins. long, 1 in. diam., firmly set, projecting 10 ins. above the ground, with brass cap mkd.,
	 1911
	WC and CC marks were scratched on cap. Add the marks AM to the stone, invert and bury in place, 18 ins. below the ground. The witness cor. to the closing cor. of secs. 15 and 16 on the easterly bdy. of the Pyramid Lake Indian Reservation Boundary no longer functions as a witness cor., and the brass cap was remarked, AM 2025, and the iron post was buried horizontally alongside the stone, 3 ins. below the ground as a memorial to the stone.
29.40	Top of main ridge, bears N. and S.

DEPENDENT RESURVEY OF A PORTION OF THE SUBDIVISIONAL LINES
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS 39.266	The true point for the 1/4 sec. cor. of sec. 9 only, determined E. of and alongside of the witness cor. to the 1/4 sec. cor. of sec. 9 only, an iron post, 36 ins. long, 1 in. diam., firmly set, in a mound of stone, 3 ft. diam., 1/2 ft. high, with brass cap mkd., S9 1/4 - WC 1911 (WC is scratched and S16 is lined out on lower half of the cap), with a vesicular basalt stone 8x8x6 ins., mkd. 1/4, out of place, lying alongside the mound of stone. Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, over a plastic-encased magnet, in a collar of stone, with brass cap mkd. T20N R24E 1/4 S 9 2025 Bury the stone alongside the base and build a mound of stone, 3 ft. base, 1 1/2 ft. high, N. of and alongside the stainless steel post. The witness cor. to the 1/4 sec. cor. of sec. 9 only, no longer functions as a witness cor., and the iron post was buried horizontally beneath the mound of stone along the N. side of the stainless steel post as a memorial to the true point. Cor. is located at the bottom of the saddle between two ridges. N. 89°42'00" W., beginning new measurement.
3.600	The true point for the 1/4 sec. cor. of sec. 16 only, determined NORTH of the monument set in 1913 for the 1/4 sec. cor. of sec. 16 only, and on the S. bdy. of sec. 9. Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 14 ins. in the ground, over a plastic-encased magnet, in a mound of stone, 4 1/2 ft. base, to top, with brass cap mkd. T20N R24E 1/4 S16 2025
5.40	From this cor. the 1913 1/4 sec. cor. of sec. 16 only, bears SOUTH, 0.046 chs. dist., monumented with an iron post, 36 ins. long, 1 in. diam., firmly set, projecting 27 ins. above the ground, in a mound of stone, 3 1/2 ft. diam., 1 ft high, with brass cap mkd. as described in the field notes of the 1913 resurvey of a portion of the subdivisional lines of T. 20 N., R. 24 E., executed under instructions dated May 10, 1913. Remark AM 2025, and bury 3 ins. below the ground, horizontally alongside the stainless steel post at the true point. The top of a conical shaped hill bears N., 1.10 chs. dist.

DEPENDENT RESURVEY OF A PORTION OF THE SUBDIVISIONAL LINES
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS 8.811	Intersect the westerly bdy. of the Pyramid Lake Indian Reservation Boundary. The true point for the closing cor. of secs. 9 and 16, at intersection of the line between secs. 9 and 16, with the westerly bdy. of the Pyramid Lake Indian Reservation Boundary. Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 15 ins. in the ground, over a plastic-encased magnet, in a mound of stone, 4 ft. base, to top, with brass cap mkd. 2025 From this point, a position monumented as the closing cor. of secs. 9 and 16 on the westerly bdy. of the Pyramid Lake Indian Reservation Boundary, during the 1887 resurvey, bears S. 3°35'40" E., 0.064 chs. dist., monumented with a basalt stone, 23x16x9 ins. (1888 Record: 15x10x8 ins.), buried in a mound of stone, 6 ft. diam., 2 ft. high, mkd., CC on upward face, PLIR on downward face. Add the marks AM to the stone, and bury it on its side, in place, 10 ins. in the ground. 32.25 Begin ascent, bears S. 10° E. and N. 10° W. 33.85 The right bank of an irrigation canal, bears N. 60° E. and S. 60° W. 34.85 The left bank of an irrigation canal, bears N. 60° E. and S. 60° W. 35.80 An irrigation canal access road, 27 lks. wide, bears N. 60° E. and S. 60° W. 43.441 The cor. of secs. 8, 9, 16 and 17.
	From the cor. of secs. 20, 21, 28 and 29. N. 89°54'10" W., bet. secs. 20 and 29. 13.00 Top of ridge, bears S. 25° E. and N. 25° W. 25.90 Draw, drains N. 20° E. 29.15 Spur, the downhill spine bears N. 15° E. 34.60 Draw, drains N. 35° E.

DEPENDENT RESURVEY OF A PORTION OF THE SUBDIVISIONAL LINES
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS	
39.903	Point for the 1/4 sec. cor. of secs. 20 and 29 at proportionate distance, there is no remaining evidence of the position of the original corner. Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 26 ins. in the ground, over a plastic-encased magnet, in a collar of stone, with brass cap mkd. T20N R24E S20 1/4 — S29 2025 Cor. is located on the E. edge of the overflow area of a wash, drains northerly.
46.923	The witness point at intersection with the Lyon and Storey County line, hereinafter described.
61.00	Spur, the downhill spine bears N. 5° W.
79.806	The cor. of secs. 19, 20, 29 and 30, monumented with a vesicular basalt stone, 14x12x8 ins. (1903 Record: 12x10x8 ins.), lying embedded in the ground, mkd. with 5 notches on an edge and 2 grooves on an adjacent face, with an embedded mound of stone, 4 ft. diam., 1/2 ft. high, along the W. side and a steel "T" post along the S. side. At the corner point Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 22 ins. in the ground, over a plastic-encased magnet, in a collar of stone, with a mound of stone, 3 ft. base, 1 1/2 ft. high along the W. side, with brass cap mkd. T20N R24E S19 S20 S30 S29 2025 Bury the mkd. stone alongside and reset the steel "T" post along the SW. side of the stainless steel post. N. 0°42'00" W., bet. secs. 19 and 20.
19.75	Draw, drains N. 55° E.
29.20	Spur, the downhill spine bears S. 75° E.
39.819	The 1/4 sec. cor. of secs. 19 and 20, monumented with a mound of stone, 3 ft. diam., 1 1/2 ft. high. This position is accepted as the best available evidence of the position of the original corner. At the corner point

DEPENDENT RESURVEY OF A PORTION OF THE SUBDIVISIONAL LINES
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS	Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 6 ins. in the ground, over a plastic-encased magnet, in a mound of stone, 6 ft. base, to top, with brass cap mkd. T20N R24E 1/4 S19 S20 2025 N. 0°28'00" E., beginning new measurement. 0.45 Top of ridge, bears N. 40° E. and S. 40° W. 9.70 Draw, drains N. 75° W. 18.20 Top of ridge, bears S. 85° E. and N. 85° W. 21.00 Draw, drains N. 80° E. 24.90 Top of ridge, bears E. and W. 40.165 The cor. of secs. 17, 18, 19 and 20, monumented with a basalt stone, 20x13x7 ins. (1903 Record: 13x10x5 ins.), firmly set, projecting 8 ins. above a mound of stone, 4 ft. diam., 1 ft. high, mkd. with 5 notches on S. edge and 3 horizontal grooves on E. face. At the corner point Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 23 ins. in the ground, over a plastic-encased magnet, in a collar of stone, with brass cap mkd. T20N R24E S18 S17 S19 S20 2025 Bury the stone alongside and build a mound of stone, 3 ft. base, 1 1/2 ft. high, along the W. side of the stainless steel post. From the cor. of secs. 16, 17, 20 and 21. S. 88°22'00" W., bet. secs. 17 and 20. 0.05 Overhead power lines, extend S. 45° E. and N. 45° W. 4.076 The witness point at intersection with the Lyon and Storey County line, hereinafter described. 5.90 Dry wash, drains N. 25° E. 33.05 Top of ridge, bears N. 10° E. and S. 10° W.
--------	--

DEPENDENT RESURVEY OF A PORTION OF THE SUBDIVISIONAL LINES
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS 36.514	The 1/4 sec. cor. of sec. 17 only, monumented with a basalt stone, 19x13x5 ins. (1903 Record: 15x10x5 ins.), firmly embedded, lying face up in an embedded mound of stone, 4 ft. diam., mkd. 1/4 on upward face. At the corner point Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 6 ins. in the ground, over a plastic-encased magnet, in a mound of stone, 4 ft. base, to top, with brass cap mkd. T20N R24E <u>1/4 S17</u> 2025 Bury mkd. stone in the mound of stone alongside the stainless steel post. N. 88°47'50" W., beginning new measurement. 3.363 The 1/4 sec. cor. of sec. 20 only, hereinafter described. 12.80 Top of steep ascent. 15.30 Top of rocky butte, bears N. 15° E. and S. 15° W. 43.234 The cor. of secs. 17, 18, 19 and 20. Point for the 1/4 sec. cor. of sec. 20 only, on the S. bdy. of sec. 17 and at midpoint in departure, between the cor. of secs. 16, 17, 20 and 21, and the cor. of secs. 17, 18, 19 and 20. Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 16 ins. in the ground, over a plastic-encased magnet, in a mound of stone, 5 ft. base, to top, with brass cap mkd. T20N R24E <u>1/4 S20</u> 2025
--------------------------	---

METES-AND-BOUNDS SURVEY OF PORTIONS OF THE
LYON AND STOREY COUNTY LINE,
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS

MEMORANDUM

The Churchill, Lyon and Storey County Lines were established by an act of the Territorial Legislature approved on November 25, 1861, entitled "An Act to Create Counties and Establish the Boundaries thereof".

On February 20, 1864, an act of the Territorial Legislature entitled, "An Act Changing the Boundary Lines of Lyon County and for Other Purposes" changed the boundaries of Churchill and Lyon County so that lands in Churchill County adjacent to Lyon County were to be ceded to Lyon County.

On March 6, 1899, the act of the Nevada State Legislature entitled, "An Act to Definitely Fix and Establish the Boundaries of Lyon County" stated that the Boundary of Storey County was not changed in the legislation since the act of 1861 and that the strip of land between the Westerly Boundary of Churchill County and the Easterly Boundary of Storey County, was ceded to Lyon County, since Lyon County had "...exercised its jurisdiction for the 5 years last past...", which made the Boundary in question common to Lyon and Storey Counties.

On April 25, 1904, a field survey was commenced to determine the location of Reed's Station and subsequent survey of the Boundary common to these counties relevant to this survey. The survey titled, "Field Notes of Survey of Eastern Boundary Storey County Nev. Being a Western Boundary of Lyon County", was executed by Thomas P. Mack, Surveyor of Lyon County, Nevada, and was filed with the Nevada State Lands Office on August 8, 1904.

On August 31, 1911, on Appeal from the District Court, Ormsby County; the Supreme Court of Nevada in Case No. 1896 affirmed the decision to deny a new trial, from the appellants (Storey County) to further dispute the location of the Boundary surveyed by Mack. It was determined that the point determined by the Mack survey as the "...northeast corner of Lyon County, and the southwest corner of Storey County...was a common point...as being three miles north of a point on the Carson River, 'one mile below Reed's Station'", and would be considered as binding, since it was made in accordance with the provisions of "An Act Authorizing the Survey and Establishment of Boundaries Between the Several Counties in this State", approved February 26. 1866.

The Mack survey consists of a plat and field notes which established monumentation at specified stationing along the Boundary, some of which differ from the notes to the plat. Monuments 10 (plat and field note station 64176.4 ft.), XI (plat station 105415.2 ft., field note station 105409.1 ft.) and XII (plat station 110580.4 ft., field note station 110924.6 ft.), were recovered, utilized and tied to determine this portion of the survey. The complete record is available in the archives of the Nevada Division of State Lands in Carson City, Nevada.

From the point for a witness point at the intersection of the Lyon and Storey County Line, with the line bet. secs., 20 and 29.

Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 26 ins. in the ground, over a plastic-encased magnet, in a collar of stone, with brass cap mkd.

METES-AND-BOUNDS SURVEY OF PORTIONS OF THE
LYON AND STOREY COUNTY LINE,
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS	
	WP T20N R24E S20 S29 2025 From this point, Monument 10 of the Lyon and Storey County Line, bears S. 28°01'50" W., 526.287 chs. dist., monumented with a granite stone, 22x8x6 ins., projecting 10 ins. above a mound of stone, 4 ft. diam., 2 ft. high, mkd. with an X on South face, S on West face, L on East face, and a cross on the top center, established by Thomas P. Mack, Lyon County Surveyor, in 1904, as shown on the Map and Field Notes of Survey of Eastern Boundary of Storey County Nev. Being a Western Boundary of Lyon County, filed in the archives of the Nevada Division of State Lands in Carson City, Nevada. Thence N. 28°01'50" E., on the Lyon and Storey County Line, through sec. 20.
25.95	On low knoll.
90.691	The point for a witness point at intersection of the Lyon and Storey County Line, with the line bet. secs. 17 and 20. Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 29 ins. in the ground, over a plastic-encased magnet, in a collar of stone, with brass cap mkd. WP T20N R24E S17 S20 2025 Build a mound of stone, 4 1/2 ft. base, 1 1/2 high, along the SW. side of the stainless steel post. Point is located, in a wash, approximately 230 lks. wide, draining generally northeasterly and in an area of heavy off highway vehicle traffic. From this point, Monument XI of the Lyon and Storey County Line, bears N. 28°01'50" E., 8.490 chs. dist., monumented with a rebar, 1/2 in. diam., firmly set, projecting 6 ins. above a mound of stone, 4 ft. diam., 1 ft. high, perpetuated by person(s) unknown, no record found. This point is accepted as the best available evidence of the position of the cor. established by Thomas P. Mack, Lyon County Surveyor, in 1904, as shown on the Map and Field Notes of Survey of Eastern Boundary of Storey County Nev. Being a Western Boundary of Lyon County, filed in the archives of the Nevada Division of State Lands in Carson City, Nevada.

METES-AND-BOUNDS SURVEY OF PORTIONS OF THE
LYON AND STOREY COUNTY LINE,
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS	
	From the point for the witness point at intersection of the Lyon and Storey County Line, with the line bet. secs., 16 and 17. Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 23 ins. in the ground, over a plastic-encased magnet, in a collar of stone, with brass cap mkd. WP T20N R24E S17 S16 2025 From this point, Monument XI of the Lyon and Storey County Line, bears S. 28°04'00" W., 0.222 chs. dist. Thence N. 28°04'00" E., on the Lyon and Storey County Line, through sec. 16. 19.60 Utility access road, bears S. 40° E. and N. 40° W. 36.85 Cross low ridge, bears S. 40° E. and N. 40° W. 79.225 The point for a witness point at intersection of the Lyon and Storey County Line, with the W. bdy. of the Pyramid Lake Indian Reservation Boundary. Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 22 ins. in the ground, over a plastic-encased magnet, in a collar of stone, with brass cap mkd. WP T20N S16 R24E PLIR 2025 From this point, Monument XII of the Lyon and Storey County Line, bears N. 28°04'00" E., 3.271 chs. dist., monumented with a mound of stone, 6 ft. diam., 3 ft. high, with a basalt stone, 16x8x6 ins., mkd. S on one face, L on the opposite face and XII on the face between the aforementioned marks, and a cross on a face above the other marks, lying alongside the mound, established by Thomas P. Mack, Lyon County Surveyor, in 1904, as shown on the Map and Field Notes of Survey of Eastern Boundary of Storey County Nev. Being a Western Boundary of Lyon County, filed in the archives of the Nevada Division of State Lands in Carson City, Nevada. Reset the stone in the top center of the mound with the marks S on the NW. side, L on the SE. side, XII on the NE. side, and the cross on top, to project 8 ins. above the mound.

METES-AND-BOUNDS SURVEY OF PORTIONS OF THE
LYON AND STOREY COUNTY LINE,
T. 20 N., R. 24 E., MOUNT DIABLO MERIDIAN, NEVADA

CHAINS	GENERAL DESCRIPTION
	The area surveyed is adjacent to the city of Fernley, Nevada, on its northwest limit. The area is drained by numerous washes which run towards the Truckee River to the north, in a westerly direction and with an irrigation canal in the northwest corner of section 16, running easterly. Vegetation consists of brushes and sparse grasses. This area is a point of suburban interface, with high recreational use, including target shooting and off highway vehicle use. The average elevation is approximately 4,400 ft. above mean sea level. Access is provided by numerous paved and dirt roads by way of U.S. Highway No. 95A.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FIELD ASSISTANTS


Lance W. Smith	Nevada Professional Land Surveyor (Experienced Services Program)
Robert S. Hollis	Surveying Technician
Mary E. Feitz	Realty Specialist
Winston H. Miller	Archeologist
Michael F. Regan	Land Law Examiner

CERTIFICATE OF SURVEY

I, Richard J. Dieckmann, Cadastral Surveyor, HEREBY CERTIFY upon honor that, in pursuance of special instructions bearing the date of the 30th day of October, 2025, I have dependently resurveyed a portion of the Pyramid Lake Indian Reservation Boundary and a portion of the subdivisional lines, and a metes-and-bounds survey of portions of the Lyon and Storey County Line, Township 20 North, Range 24 East, of the Mount Diablo Meridian, in the State of Nevada, which are represented in the foregoing field notes as having been executed by me and under my direction; and that said survey has been made in strict conformity with said special instructions, the Manual of Instructions for the Survey of the Public Lands of the United States, and in specific manner described in the foregoing field notes.

AUG 20 2026

(Date)



(Cadastral Surveyor)


CERTIFICATE OF APPROVAL

BUREAU OF LAND MANAGEMENT
Reno, Nevada

The foregoing field notes of the dependent resurvey of a portion of the Pyramid Lake Indian Reservation Boundary and a portion of the subdivisional lines, and a metes-and-bounds survey of portions of the Lyon and Storey County Line, Township 20 North, Range 24 East, of the Mount Diablo Meridian, Nevada, executed by Richard J. Dieckmann, Cadastral Surveyor, having been critically examined and found correct, are hereby approved.

AUG 21 2026

(Date)



(Chief Cadastral Surveyor for Nevada)

~~CERTIFICATE OF TRANSCRIPT~~

~~I CERTIFY that the foregoing transcript of the field notes of the above described surveys in Township 20 North, Range 24 East, Mount Diablo Meridian, Nevada, is a true copy of the original field notes.~~

~~(Date)~~

~~(Chief Cadastral Surveyor for Nevada)~~